


Risk Analysis of the Influence of Work Methods, Equipment and K3, and Land Affected by the Community on the Implementation of the Coastal Safety Development Project on the Coastal Jakarta Bay Phase 6 Package 4

Kurniawan Widhitomo¹, Moh. Azhar², Sri Kustoyo Raharjo³

^{1,2,3}Master of Civil Engineering, Universitas Tama Jagakarsa, Indonesia

| Article Info | ABSTRACT |
|--|--|
| Keywords: Rob, Work Methods, K3, Social and Land. | DKI Jakarta Province and its surroundings often experience flood events. The causes of flooding include increased rainfall intensity, large-scale land conversion and insufficient river capacity to accommodate flood discharge. In addition, land subsidence in several locations of Jakarta Beach caused a storm that inundated residential areas and other strategic areas. Related to that, the construction of embankments and the construction of coastal safety needs to be carried out. In the implementation of the work there are problems such as the working method of Equipment, K3, Social community and land, the four problems do affect the time of project implementation, the scope of this research is carried out in the project package 4 coastal safety of the capital and the project is still running. The purpose of this study is to determine the influence of occupational safety risks, equipment, and the social influence of the community around the project on the implementation time. Meanwhile, data is taken either secondary (work reports or other literature, both secondary and primary). |
| This is an open access article under the CC BY-NC license  | Corresponding Author: Kurniawan Widhitomo Master of Civil Engineering, Universitas Tama Jagakarsa, Indonesia kurniawan.widhitomo@gmail.com |

INTRODUCTION

DKI Jakarta Province and its surroundings often experience flood events. The causes of flooding include increased rainfall intensity, large-scale land conversion and insufficient river capacity to accommodate flood discharge, and rob that inundated residential areas and other strategic areas. This activity is divided into 3 (three) zones, namely Zone A, Zone B and Zone C.

Coastal infrastructure development projects face various challenges, especially related to operational risks and environmental impacts. Various literatures support the importance of a thorough risk analysis to address various factors that can affect the smooth and successful operation of large-scale construction projects, especially in dense urban areas such as Jakarta Bay.

According to the Project Management Institute (PMI), construction project risks can be identified through quantitative and qualitative analysis approaches to evaluate their impact

on project cost, time, and quality (Project Management Institute, 2017). This approach supports project management by providing a framework to address the uncertainties that arise, especially in projects involving local community conditions and the dependence on heavy equipment that was also identified in the coastal safety project in Jakarta Bay. The efficiency and effectiveness of equipment are the determining factors for the success of a construction project. According to Mardiaman (2023), equipment that is damaged or does not function optimally can hinder smooth operations and reduce the project's daily productivity. In the field, this coastal safety construction project faces significant obstacles due to damage to heavy equipment such as cranes and pontoons which cause delays in dredging work (Mardiaman, 2020). This underscores the importance of regular equipment maintenance and inspections to minimize the risk of delays.

In the context of construction work, the implementation of occupational health and safety (OHS) is very important to reduce the risk of accidents that can affect the running of the project. Ridley (2006) in the Overview of Occupational Health and Safety stated that the lack of detail in work methods and the absence of risk assessment in each activity can increase the likelihood of work accidents. In this project, the analysis of work methods and occupational safety was identified as a source of risk that had the potential to cause delays, so the application of more structured work methods and detailed risk evaluation were needed (Ridley, 2006). According to Gunawan (2012) in Construction Project Management, community involvement can minimize social barriers and assist project management in managing the expectations of the affected communities. Based on a survey conducted in the Jakarta Bay project, the surrounding community expressed concern about the impact of vibration, noise, and the risk of eviction. This emphasizes the need for transparency, fair compensation, and regular socialization to affected communities to reduce the potential for conflict (Gunawan, 2017). The following is a picture of the division of work zones:



Figure 1. Job Location

Draw the work plan as follows:



Figure 2. Work plan

Various studies show that the success of construction projects is greatly influenced by risk management which includes work methods, equipment conditions, occupational health and safety, and social impacts on the surrounding community. This study enriches the study in construction risk management, especially in infrastructure projects in urban areas with high interaction with the surrounding environment and local communities. There are several problems that may affect project delays, namely:

1. Social issues
2. Equipment problems
3. Job safety

The purpose of the study is to determine the influence of occupational safety risks, equipment, and the social influence of the community around the project on the implementation time.

METHODS

The systematics of writing research is qualitative and quantitative, both observation data is disposed, then analyzed, and if necessary, questioner to obtain statistical data, related to the research.

RESULTS AND DISCUSSION

Spun Pile Piling

PT. CIRIAJASA E.C. KSO HA - HWK

SPUN PILE PILING DATA RECORD



COASTAL SAFETY DEVELOPMENT PROJECT ON THE COAST OF
 JAKARTA BAY PHASE 6 PACKAGE 4

BY: INSPECTOR

| No | Date | SP Length | Zone | Description | Anchored Per Day | Total SP Staked | Information |
|----|--------------------------|-----------|------|-------------|------------------|-----------------|---|
| 1 | Wednesday, 19 April 2023 | 24m | C | SP1 | 1 | 1 | Trial Hoisting |
| 2 | Wednesday, 03 May 2023 | 24m | C | SP2 - SP4 | 3 | 4 | Spun Pile Piling Using Innerboring Tools Start Slightly Noon |
| 3 | Thursday, 04 May 2023 | 24m | C | SP5 - SP8 | 4 | 8 | |
| 4 | Friday, 05 May 2023 | 24m | C | SP9 - SP10 | 2 | 10 | Matrial Spun Pile Stock in Pontoons Runs Out, Waiting for Curtains to Install |

Risk Analysis of the Influence of Work Methods, Equipment and K3, and Land Affected by the Community on the Implementation of the Coastal Safety Development Project on the

Coastal Jakarta Bay Phase 6 Package 4—Kurniawan Widhitomo et.al

| | | | | | | | |
|----|------------------------|-----|---|-------------|---|----|--|
| 5 | Saturday, 06 May 2023 | 24m | C | SP11 - SP13 | 3 | 13 | Solar Morning Innerboring Tool Runs Out Waiting for Solar, Start at Noon |
| 6 | Sunday, 07 May 2023 | 24m | C | SP14 - SP16 | 3 | 16 | Afternoon Wait for Coordination of Pontoon Shift |
| 7 | Monday, 08 May 2023 | 24m | C | SP17 - SP20 | 4 | 20 | |
| 8 | Tuesday, 09 May 2023 | 24m | C | SP21 - SP24 | 4 | 24 | |
| 9 | Wednesday, 10 May 2023 | 24m | C | SP25 - SP29 | 5 | 29 | |
| 10 | Thursday, 11 May 2023 | 24m | C | SP30 - SP34 | 5 | 34 | |
| 11 | Friday, 12 May 2023 | 24m | C | SP35 - SP39 | 5 | 39 | |
| 12 | Saturday, 13 May 2023 | 24m | C | SP40 - SP44 | 5 | 44 | |
| 13 | Sunday, 14 May 2023 | 24m | C | SP45 - SP47 | 3 | 47 | |
| 14 | Monday, 15 May 2023 | 24m | C | SP48 - SP50 | 3 | 50 | |
| 15 | Friday, 09 June 2023 | 24m | C | SP51 - SP54 | 4 | 54 | May 16 to June 8 Wait for Kamal Citizen Socialization |
| 16 | Saturday, 10 June 2023 | 24m | C | SP55 - SP58 | 4 | 58 | |
| 17 | Monday, 12 June 2023 | 24m | C | SP59 - SP62 | 4 | 62 | June 11 Closed |
| 18 | Tuesday, 13 June 2023 | 24m | C | SP63 - SP66 | 4 | 66 | |
| 19 | Thursday, 15 June 2023 | 24m | C | SP67 - SP70 | 4 | 70 | June 14 Replace the Fanbelt of the Inner Boring Tool |
| 20 | Saturday, 17 June 2023 | 24m | C | SP71 - SP75 | 5 | 75 | June 16 Rainy Field Conditions |
| 21 | Sunday, 18 June 2023 | 24m | C | SP76 - SP80 | 5 | 80 | |
| 22 | Monday, 19 June 2023 | 24m | C | SP81 - SP83 | 3 | 83 | |
| 23 | Tuesday, 20 June 2023 | 24m | C | SP84 - SP87 | 4 | 87 | |

| | | | | | | | |
|----|------------------------------|-----|---|---------------|---|-----|---|
| 24 | Wednesday, 21 June 2023 | 24m | C | SP88 - SP91 | 4 | 91 | |
| 25 | Thursday, 22 June 2023 | 24m | C | SP92 - SP95 | 4 | 95 | Total in Zone C 95 Stems |
| 26 | Thursday, 21 September 2023 | 24m | A | SP96 | 1 | 96 | First Planting in Zone A |
| 27 | Friday, 22 September 2023 | 24m | A | SP97 - SP99 | 3 | 99 | |
| 28 | Saturday, 23 September 2023 | 24m | A | SP100 - SP101 | 2 | 101 | Morning Innerboring Tool Damaged Hose |
| 29 | Sunday, 24 September 2023 | 24m | A | SP102 - SP104 | 3 | 104 | Broken Tugboat |
| 30 | Monday, 25 September 2023 | 24m | A | SP105 | 1 | 105 | Tugboat Damaged Commitment at 5 Ready Hour |
| 31 | Tuesday, 26 September 2023 | 24m | A | SP106 - SP109 | 4 | 109 | |
| 32 | Wednesday, 27 September 2023 | 24m | A | SP110 - SP113 | 4 | 113 | |
| 33 | Thursday, 28 September 2023 | 24m | A | SP114 - SP120 | 7 | 120 | |
| 34 | Friday, 29 September 2023 | 24m | A | SP121 - SP124 | 4 | 124 | |
| 35 | Wednesday, 04 October 2023 | 24m | A | SP125 - SP131 | 7 | 131 | |
| 36 | Thursday, 05 October 2023 | 24m | A | SP132 - SP137 | 6 | 137 | |
| 37 | Friday, 06 October 2023 | 24m | A | SP138 - SP145 | 8 | 145 | |
| 38 | Saturday, 14 October 2023 | 24m | A | SP146 | 1 | 146 | Morning Curtain Material and Waiting for the Installation |
| 39 | Sunday, 15 October 2023 | 24m | A | SP147 - SP153 | 7 | 153 | |


| | | | | | | | |
|----|----------------------------------|-----|---|------------------|---|-----|---|
| 40 | Monday, October 16, 2023 | 24m | A | SP154 - 155 | 2 | 155 | Auger Alat Inner Boring Macet |
| 41 | Wednesday, 18 October 2023 | 24m | A | SP156 - SP162 | 7 | 162 | |
| 42 | Friday, 20 October 2023 | 24m | A | SP163 | 1 | 163 | Start of staking at 16.00 |
| 43 | Saturday, 21 October 2023 | 24m | A | SP164 - SP169 | 6 | 169 | |
| 44 | Thursday, 02 November 2023 | 24m | A | SP170 - SP171 | 2 | 171 | Morning Curtain Material Starts Piling at 13.00 |
| 46 | Friday, 03 November 2023 | 24m | A | SP172 - SP179 | 8 | 179 | |
| 48 | Sunday, 05 November 2023 | 24m | A | SP180 - SP181 | 2 | 181 | |
| 50 | Monday, 06 November 2023 | 24m | A | SP182 - SP189 | 8 | 189 | |
| 52 | Monday, 13 November 2023 | 24m | A | SP190 - SP197 | 8 | 197 | |
| 54 | Tuesday, November 14, 2023 | 24m | A | SP198 | 1 | 198 | Start staking at 09:00 after that curtain material because the stock in the pontoon runs out |
| 56 | Wednesday, 15 November 2023 | 24m | A | SP199 - 201 | 3 | 201 | |
| 58 | Thursday, 16 November 2023 | 24m | A | SP202 - 209 | 8 | 209 | |
| 60 | Friday, 17 November 2023 | 24m | A | SP210 - SP217 | 8 | 217 | |
| 62 | Saturday, 18 November 2023 | 24m | A | SP218 | 1 | 218 | Stake starts at 13.00 |
| 64 | Monday, 20 November 2023 | 24m | A | SP219 - SP227 | 9 | 227 | |
| 66 | Thursday, 23 November 2023 | 24m | A | SP228 - SP234 | 7 | 234 | |
| 68 | Friday, 24 November 2023 | 24m | A | SP235 - SP237 | 3 | 237 | Stake starts at 13.00 |
| 70 | Saturday, 25 November 2023 | 24m | A | SP238 - SP244 | 7 | 244 | |
| 72 | Sunday, 26 November 2023 | 24m | A | SP245 | 1 | 245 | Stopped because Waiting for |


| | | | | | | | Residents' Land Acquisition |
|----|-----------------------------|-----|---|---------------|---|-----|---|
| 73 | Wednesday, 20 December 2023 | 24m | A | SP363 | 1 | 246 | Piling Jumps to SP363 Because the Land Is Not Ready |
| 74 | Thursday, 21 December 2023 | 24m | A | SP362-359 | 4 | 250 | Stopped because Waiting for Residents' Land Acquisition |
| 75 | Thursday, 11 January 2024 | 24m | A | SP246 | 1 | 251 | At 15.00 Start Stake Can 1 Continue to Rain |
| 76 | Friday, 12 January 2024 | 24m | A | SP247 - SP248 | 2 | 253 | Morning continues at 08.00 Continue SP246 Continue Curtain material at 14.30 Start Pile SP247 & 248 Then stop due to low tide |
| 77 | Saturday, 13 January 2024 | 24m | A | SP249 - SP250 | 2 | 255 | At 14.00 Start Stake Can 1 Continue to Rain |
| 78 | Sunday, 14 January 2024 | 24m | A | SP251 - SP253 | 3 | 258 | |
| 79 | Monday, January 15, 2024 | 24m | A | SP254 - SP255 | 2 | 260 | |
| 80 | Tuesday, January 16, 2024 | 24m | A | SP256 - SP259 | 4 | 264 | |
| 81 | Wednesday, 17 January 2024 | 24m | A | SP260 - SP266 | 7 | 271 | |
| 82 | Thursday, January 18, 2024 | 24m | A | SP267 - SP273 | 7 | 278 | |
| 83 | Thursday, January 25, 2024 | 24m | A | SP274 - SP280 | 7 | 285 | |
| 84 | Sunday, January 28, 2024 | 24m | A | SP281 - SP287 | 7 | 292 | |
| 85 | Tuesday, 30 January 2024 | 24m | A | SP288 - SP294 | 7 | 299 | |
| 86 | Saturday, 03 February 2024 | 24m | A | SP295 | 1 | 300 | Crane Material Boom Picked |

| | | | | | | | Wednesday - Friday |
|-----|-----------------------------|-----|---|----------------|---|-----|--------------------|
| 87 | Sunday, 04 February 2024 | 24m | A | SP296 - SP297 | 2 | 302 | |
| 88 | Tuesday, 06 February 2024 | 24m | A | SP298 - SP301 | 4 | 306 | |
| 89 | Thursday, 08 February 2024 | 24m | A | SP302 - SP304 | 3 | 309 | |
| 90 | Friday, 09 February 2024 | 24m | A | SP305 | 1 | 310 | |
| 91 | Friday, 16 February 2024 | 24m | A | SP306 | 1 | 311 | |
| 92 | Saturday, February 17, 2024 | 24m | A | SP307 - SP309 | 3 | 314 | |
| 93 | Sunday, 18 February 2024 | 24m | A | SP310 - SP312 | 3 | 317 | |
| 94 | Monday, February 19, 2024 | 24m | A | SP313 - SP316 | 4 | 321 | |
| 95 | Wednesday, 21 February 2024 | 24m | A | SP317 - SP 319 | 3 | 324 | |
| 96 | Thursday, February 22, 2024 | 24m | A | SP320 - SP321 | 2 | 326 | |
| 97 | Monday, February 26, 2024 | 24m | A | SP322 - SP323 | 2 | 328 | |
| 98 | Tuesday, 27 February 2024 | 24m | A | SP324 - SP326 | 3 | 331 | |
| 99 | Friday, 08 March 2024 | 24m | A | SP327 - SP329 | 3 | 334 | |
| 100 | Sunday, March 10, 2024 | 24m | A | SP330 - SP333 | 4 | 338 | |
| 101 | Monday, March 11, 2024 | 24m | A | SP334 - SP336 | 3 | 341 | |
| 102 | Tuesday, 12 March 2024 | 24m | A | SP337 - SP340 | 4 | 345 | |
| 103 | Saturday, 16 March 2024 | 24m | A | SP341 - SP342 | 2 | 347 | |
| 104 | Sunday, 17 March 2024 | 24m | A | SP343 - SP345 | 3 | 350 | |
| 105 | Tuesday, 19 March 2024 | 24m | A | SP346 - SP347 | 2 | 352 | |

| | | | | | | | |
|-----|-----------------------------|-----|---|------------------|---|-----|---------------|
| 106 | Wednesday, 20 March 2024 | 24m | A | SP348 | 1 | 353 | |
| 107 | Thursday, 21 March 2024 | 24m | A | SP349 - SP351 | 3 | 356 | |
| 108 | Friday, 22 March 2024 | 24m | A | SP352 - SP356 | 5 | 361 | |
| 109 | Saturday, 23 March 2024 | 24m | A | SP357 - SP358 | 2 | 363 | FINISH |

Production Capacity Based on Direct Observation in the Field:

| Crawler Crane | | | |
|--|------------------------------------|--------------|------------|
| | Variable | Parameter | Unit |
|  | Type | - | |
| | Equipment Efficiency Factor (Fadt) | 0,8 | |
| | Lift Capacity | 1 | Pile |
| | Loading Time (T1) | 3,2833333333 | Minutes |
| | Travel Time with Load (T2) | 7,7333333333 | Minutes |
| | Cycle Time (Ts) | 11,01666667 | Minutes |
| | Production Capacity (Q) | 4,357034796 | Piles/Hour |
| | Equipment Coefficient | 0,229513889 | Hour |
| | Equipment Coefficient | 1,836111111 | day |

| Inner Boring and Pile Driving Rig | | | |
|---|------------------------------------|--------------|------------|
| | Variable | Parameter | Unit |
|  | Type | | |
| | Bore Pile Depth | 24 | m |
| | Bore Diameter | 1,8 | m |
| | Capacity (V) | 1 | Point |
| | Equipment Efficiency Factor (Fadt) | 0,8 | |
| | Bore Point Checking Time | 1 | Minutes |
| | Equipment Preparation Time | 30 | Minutes |
| | Tool Firmness Check Time | 5,1333333333 | Minutes |
| | Drill Bit Connecting Time | 12,71666667 | Minutes |
| | Pre-boring Time | 11,383333333 | Minutes |
| | Cleaning Time | 3,766666667 | Minutes |
| | Top Hat Installation Time | 1,916666667 | Minutes |
| | Total Boring and Pile Driving Time | 23,85 | Minutes |
| | Pulling Drill Bit Time | 2,346388889 | Minutes |
| | Cycle Time (TS) | 92,11 | Minutes |
| | Production Capacity (Q) | 0,52 | Point/Hour |
| | Equipment Coefficient | 1,919 | Hour |

Risk Analysis of the Influence of Work Methods, Equipment and K3, and Land Affected by the Community on the Implementation of the Coastal Safety Development Project on the

Coastal Jakarta Bay Phase 6 Package 4–Kurniawan Widhitomo et.al

| | | | |
|--|-----------------------|--------|-----|
| | Equipment Coefficient | 15,352 | day |
|--|-----------------------|--------|-----|

| Time Stamp Spun Pile Driving Based on Video | | | |
|---|---|---|---------------------|
| HE Type | Categories | Description | Time (s) |
| Crawler Crane | Cycle Time (Move + Swing) | Before lifting | 73 |
| | Cycle Time (Connecting + Lifting) | Connecting the winch with spun pile | 124 |
| | Cycle Time (Swing) | After Connecting, Placing pile, Connector removal | 464 |
| Inner Boring Rig | Bore Point Checking Time | | 60 |
| | Equipment Preparation Time (Bracing Installation) | | 1800 |
| | Tool Firmness Check Time | | 308 |
| | Drill Bit Connecting Time | | 763 |
| | Pre-boring Time | | 683 |
| | Cleaning Time | | 226 |
| | Top Head Installation Time | | 115 |
| Total Boring and Pile Driving Time | | 1431 | |
| Spun Pile Mobilization | Mobilization of Spun Pile to the Pontoon | | 2400 |
| Total Cycle Time for 1 Spun Pile (min) | | | 140,78333333 |

| | |
|--------------------------------|-------------|
| Working Hours (Min) | 480 |
| Cycle Time For 1 Pile (Min) | 70,78333333 |
| Bracing Intallation Time (Min) | 30 |
| Spun Pile Mobilization (Min) | 40 |
| Number of Pile in 1 Day | 5,792323993 |

Field Real Pile Production Capacity

| | | |
|----------------|----------------|--------------------------------------|
| Number of Days | Number of Rods | Real Bar Production Capacity Per Day |
| 335 | 363 | 1,08358209 |

Stake Production Capacity Based on Shcedule Contract

| | | |
|----------------|----------------|--|
| Number of Days | Number of Rods | Rod Production Capacity Per Day Schedule |
| 303 | 363 | 1,198019802 |

Contract Deviation Vs Real

| | | |
|----------------|----------------|--|
| Number of Days | Number of Rods | Bar-Day Production Capacity -Real Contract |
| 32 | 363 | 0,114437712 |

Real Vs Contract Production Capacity (Rod)

| Production Capacity Per Day | Number of Stems Per Day |
|-----------------------------|-------------------------|
| Real | 1,08358209 |
| Contract | 1,198019802 |
| Deviation | 0,114437712 |

Real Vs Contract Production Capacity (Days)

| Production Capacity | Number of Days |
|---------------------|----------------|
| Real | 335 |
| Contract | 303 |
| Deviation | 32 |

Number of Stems Per Day

| Production Capacity Per Day | Number of Stems Per Day |
|-----------------------------|-------------------------|
| Real | 1,08358209 |
| Contract | 1,198019802 |
| Observation | 5,792323993 |

Rod Per Heart Vs Time

| Production Capacity Per Day | Number of Stems Per Day | Time |
|-----------------------------|-------------------------|-------------|
| Real | 1,08358209 | 335 |
| Contract | 1,198019802 | 303 |
| Observation | 5,792323993 | 62,66914634 |

Time Efficiency Compared to Observation

| Production Capacity Per Day | Time (Days) | Efficiency |
|-----------------------------|-------------|-------------|
| | | |
| Real | 335 | 272,3308537 |
| Contract | 303 | 240,3308537 |
| Observation | 62,66914634 | 0 |

Real Time Efficiency Vs Observation


| Production Capacity Per Day | Time (Days) | Efficiency |
|-----------------------------|-------------|-------------|
| Real | 335 | 272,3308537 |
| Observation | 62,66914634 | |

Contract Time Efficiency Vs Observation

| Production Capacity Per Day | Time (Days) | Efficiency |
|-----------------------------|-------------|-------------|
| Contract | 303 | 240,3308537 |
| Observation | 62,66914634 | |

Square pile productivity

Based on observations:

| Crawler Crane with Pile Drive Hammer | | | |
|---|------------------------------------|--------------|----------|
| | Variable | Parameter | Unit |
|  | Type | - | |
| | Equipment Efficiency Factor (Fadt) | 0,8 | |
| | Lift Capacity | 60,24 | Ton |
| | Loading Time (T1) | 8,183333333 | Minutes |
| | Travel Time with Load (T2) | 10,783333333 | Minutes |
| | Cycle Time (Ts) | 28,833333333 | Minutes |
| | Production Capacity (Q) | 100,2839306 | Ton/Hour |
| | Equipment Coefficient | 0,009971687 | Hour |
| | Equipment Coefficient | 0,001246461 | day |

| Time Stamp Spun Pile Driving Based on Video | | | |
|---|-----------------------------------|---|----------|
| HE Type | Categories | Description | Time (s) |
| Crawler Crane (Material Mobilization) | Cycle Time (Move + Swing) | Before lifting | 83 |
| | Cycle Time (Connecting + Lifting) | Connecting the winch with square pile | 143 |
| | Cycle Time (Swing) | After Connecting, Placing pile, Connector removal | 378 |
| | Material Hauling | Crossing the river | 840 |
| | Cycle Time (Move + Swing) | Before lifting | 112 |
| | Cycle Time (Connecting + Lifting) | Connecting the winch with square pile | 163 |
| | Cycle Time (Swing) | After Connecting, Placing pile, Connector removal | 378 |
| Crawler Crane (Pile Drive Hammer) | Bore Point Checking Time | | 60 |
| | Equipment Preparation Time | | 300 |
| | Pile Drive Hammer Connecting Time | | 491 |
| | Hammer Connecting to Square Pile | | 274 |
| | Hammering Time | | 532 |
| | Welding Time (Connecting 2 piles) | | 721 |
| | Hammering Time | | 115 |
| Disconnecting Hammer | | 244 | |

Risk Analysis of the Influence of Work Methods, Equipment and K3, and Land Affected by the Community on the Implementation of the Coastal Safety Development Project on the

Coastal Jakarta Bay Phase 6 Package 4–Kurniawan Widhitomo et.al

| | |
|---|--------------------|
| Total Cycle Time for 1 Spun Pile (min) | 80,56666667 |
|---|--------------------|

| | |
|-------------------------------------|--------------------|
| Working Hours (Min) | 480 |
| Cycle Time For 1 Pile (Min) | 45,61666667 |
| Spun Pile Mobilization (Min) | 34,95 |
| Number of Pile in 1 Day | 9,756302521 |

Based on the real data as follows:



PT. CIRIAJASA E.C. KSO HA - HWK
RECORD DATA ON SQUARE PILE PILING ZONE A PIER
COASTAL SAFETY DEVELOPMENT PROJECT ON THE COAST OF
JAKARTA BAY PHASE 6 PACKAGE 4
BY : INSPECTOR

| No | Date | Square Pile Length | Zone | Description | Ancored Per Day | Total CC SP Staked | Information |
|----|-----------------------------|--------------------|------|----------------------------|-----------------|--------------------|---|
| 1 | Sunday, January 28, 2024 | 10m + 10m | A | L38-A | | | L38-A Breaks Up and Plans to Move Point |
| 2 | Wednesday, January 31, 2024 | 10m + 10m | A | L38-B | | 0 | L38-B Breaks Up and Plans Move Point Defended |
| 3 | Friday, 02 February 2024 | 10m + 10m | A | L37-B, L36-B | 2 | 2 | |
| 4 | Saturday, 03 February 2024 | 10m + 10m | A | D17-E, D16-E, D15-E | 3 | 5 | |
| 5 | Sunday, 04 February 2024 | 10m + 10m | A | D17-D, D14-E | 2 | 7 | |
| 6 | Monday, 05 February 2024 | 10m + 10m | A | D13-E, D12-E, D18-D, D18-E | 4 | 11 | |
| 7 | Tuesday, 06 February 2024 | 10m + 10m | A | L36-C, L35-C | 2 | 13 | |

Risk Analysis of the Influence of Work Methods, Equipment and K3, and Land Affected by the Community on the Implementation of the Coastal Safety Development Project on the

Coastal Jakarta Bay Phase 6 Package 4—Kurniawan Widhitomo et.al

| | | | | | | | |
|----|-----------------------------------|-----------------|---|--|---|----|--|
| 8 | Wednesday, 07 February 2024 | 10m + 10m | A | L34-C, L37-C, L38C | 3 | 16 | |
| 9 | Friday, 09 February 2024 | 10m + 10m | A | L35-B, L34-B, L33- B | 3 | 19 | |
| 10 | Saturday, February 10, 2024 | 10m + 10m | A | L32-B, L33-C, L32- C | 3 | 22 | |
| 11 | Sunday, 11 February 2024 | 10m + 10m | A | L31-C, D16-D, D15-D | 3 | 25 | |
| 12 | Monday, February 12, 2024 | 10m + 10m | A | D14-D, D13-D, D12-D, D11-D | 4 | 29 | |
| 13 | Tuesday, 13 February 2024 | 10m + 10m | A | L37-A, L36-A, L35- A, L34-A | 3 | 32 | L35-A Breaks Up and Plans Move Point Defends |
| 14 | Thursday, 15 February 2024 | 10m + 10m | A | L33-A, L32-A, L30- C, L29-C, L28 C | 5 | 37 | Day 14 Presidential Election Holiday |
| 15 | Friday, 16 February 2024 | 10m + 10m | A | L27-C, L26-C, L31- B, L30-B, L29-B | 5 | 42 | |
| 16 | Saturday, February 17, 2024 | 10m + 10m | A | L28-B, L27B, L26B, D10-D, D9-D | 5 | 47 | |
| 17 | Sunday, 18 February 2024 | 10m + 10m | A | D8-D, D7-D, D6-D, D5-D, D11-E, D10E | 6 | 53 | |
| 18 | Monday, February 19, 2024 | 10m + 10m | A | D9D, D8E, D7E, D6E, D5E | 5 | 58 | |
| 19 | Tuesday, 20 February 2024 | 10m + 10m | A | L31A, L30A, L29A, L28A, L27A, L26A | 6 | 64 | |
| 20 | Wednesday, 21 February 2024 | 10m + 10m | A | D4D, D3D, D2D, D1D | 4 | 68 | |
| 21 | Thursday, February 22, 2024 | 10m + 10m | A | D4E, D3E, D2E, D1E, L25C, L24C, L23C | 7 | 75 | |

| | | | | | | | |
|--------|-----------------------------------|-----------------|---|---------------------------------------|---|---------|-----------------------------------|
| 2 2 | Friday, 23 February 2024 | 10m + 10m | A | D22C, D21C, D20C | 3 | 78 | Top Pile Repair |
| 2 3 | Saturday, February 24, 2024 | 10m + 10m | A | L25B, L24B, L23B, L22B, L25A, L24A | 6 | 84 | |
| 2 4 | Sunday, 25 February 2024 | 10m + 10m | A | L23A, L22A, L21A, L20A, L19C, L18C | 6 | 90 | |
| 2 5 | Monday, February 26, 2024 | 10m + 10m | A | L17C, L16C, L15C, L14C | 4 | 94 | Crane Service Alternate Repair |
| 2 6 | Tuesday, 27 February 2024 | 10m + 10m | A | L19A, L18A, L17A | 3 | 97 | |
| 2 7 | Wednesday, 28 February 2024 | 10m + 10m | A | L16A, L15A, L14A, L13C, L12C | 5 | 10 2 | |
| 2 8 | Thursday, 29 February 2024 | 10m + 10m | A | L11C, L10C, L9C | 3 | 10 5 | |
| 2 9 | Friday, 01 March 2024 | 10m + 10m | A | L18C, L13A, L12A, L11A, L10A | 5 | 11 0 | |
| 3 0 | Saturday, 02 March 2024 | 10m + 10m | A | L9A, L8A, L7C, L6C, L5C, L4C | 6 | 11 6 | |
| 3 1 | Monday, 04 March 2024 | 10m + 10m | A | L3C, L2C, L7A, L6A, L5A, L4A | 6 | 12 2 | |
| 3 2 | Tuesday, 05 March 2024 | 10m + 10m | A | L3A, L2A, L1C, L1A | 4 | 12 6 | |
| 3 3 | Wednesday, 06 March 2024 | 10m + 10m | A | L35A, L39C, L40C, L41C | 4 | 13 0 | L35A Fixed |
| 3 4 | Thursday, 07 March 2024 | 10m + 10m | A | L39A, L40A, L41A, L39B, L38A | 5 | 13 5 | L38A Fixed |
| 3 5 | Friday, 08 March 2024 | 10m + 10m | A | L38B, L42C, L43C, L44C | 4 | 13 9 | L38B has been fixed |

| | | | | | | | |
|--------|------------------------------|-----------------|---|---------------------------------------|---|---------|---------------|
| 3 6 | Saturday, 09 March 2024 | 10m + 10m | A | L45C | 1 | 14 0 | |
| 3 7 | Sunday, March 10, 2024 | 10m + 10m | A | L46C, L47C, L42A, L43A, L44A, L45A | 6 | 14 6 | |
| 3 8 | Wednesday, March 13, 2024 | 10m + 10m | A | L46A, L45A, L48C, L49C, L50C, L48A | 6 | 15 2 | |
| 3 9 | Thursday, March 14, 2024 | 10m + 10m | A | L49A, L50A, L51C, L53C, L54C, L55C | 7 | 15 9 | |
| 4 0 | Friday, 15 March 2024 | 10m + 10m | A | L56C, L51A, L52A, L53A, L54A | 5 | 16 4 | |
| 4 1 | Saturday, 16 March 2024 | 10m + 10m | A | 55A, 56A, 57C, 58C, 59C | 5 | 16 9 | |
| 4 2 | Sunday, 17 March 2024 | 10m + 10m | A | L57A, L58A, L59A, L60A, L60C | 5 | 17 4 | FINISH |

| Field Real Pile Production Capacity | | |
|-------------------------------------|----------------|----------------------------------|
| Number of Days | Number of Rods | Real Production Capacity Per Day |
| 40 | 174 | 4,35 |

| Days Required | | |
|---------------|----------------------|--|
| Planting Plan | Based on Observation | Days Required Based on Observations on Lap |
| 174 | 9,756302521 | 17,83462532 |

| Field Efficiency | | |
|-----------------------------|-------------|-------------------|
| Production Capacity Per Day | Time (Days) | Efficiency (Days) |
| Real | 40 | |
| Observation | 18 | |
| Total | | 22 |

CCSP Production

Ccsp Hoisting Schedule

| No | Piling | 2023 | | | 2024 | | | | | | | | |
|----|--------|------|-----|-----|------|-----|-----|-----|-----|-----|-----|-----|------|
| | | Okt | Nov | Des | Jan | Feb | Mar | Apr | Mei | Jun | Jul | Agt | Sept |
| | | 10 | 11 | 12 | 13 | 14 | 15 | 16 | 17 | 18 | 19 | 20 | 21 |
| 1 | W 400 | 89 | 89 | 89 | 89 | 89 | 89 | 89 | 89 | 89 | 89 | 89 | 89 |

| | | | | | | | | | | | | |
|---|------|--|--|--|--|----|----|----|----|----|----|----|
| 2 | W450 | | | | | 88 | 88 | 89 | 89 | 89 | 89 | 89 |
|---|------|--|--|--|--|----|----|----|----|----|----|----|

CCSP Plan Until May

| No | Piling | 2023 | | | 2024 | | | | | Total Target |
|----|--------|------|-----|-----|------|-----|-----|-----|-----|--------------|
| | | Okt | Nov | Des | Jan | Feb | Mar | Apr | Mei | |
| | | 10 | 11 | 12 | 13 | 14 | 15 | 16 | 17 | |
| 1 | W 400 | 89 | 89 | 89 | 89 | 89 | 89 | 89 | 89 | 712 |
| 2 | W450 | | | | | 88 | 88 | 89 | 89 | 354 |

Target Vs Real

| No | Piling | Total Target | Real | Deviation |
|----|--------|--------------|------|-----------|
| 1 | W 400 | 712 | 276 | -436 |
| 2 | W450 | 354 | 275 | -79 |

CCSP Installation Production Capacity Per Day Based On Field Data

| No | Piling | Sum | Day | Rod / Day |
|----|--------|-----|-----|-------------|
| 1 | W 400 | 276 | 33 | 8,363636364 |
| 2 | W450 | 275 | 33 | 8,333333333 |

Working Methods / CSA



CSA Format image without hazard column list



CSA Format Image with Hazard column

In the construction safety analyst form, it can be seen that the work method is less detailed and there is no danger or risk column as a result, detailed method is very necessary to anticipate accidents during implementation, where if an accident occurs it will have an impact on the implementation time. For example, the addition of a hazard column is indispensable and detailing the work method during implementation.

Community Conditions

The condition of the community around the project greatly affects the continuity of the coastal retaining embankment project. Such as related to the demolition of houses in the area where the project is located or being hit by the installation path of spun pile or ccsp, or others related to the coastal retaining embankment. We conducted a direct survey of the community around the project with 51 people with the following results:

| No | The two biggest scores | Nilai | |
|----|--|-------|--------|
| | | Angka | Persen |
| 1 | Approve the development | 30 | 59% |
| | Strongly agree | 9 | 17% |
| 2 | Beneficial Development | 27 | 53% |
| | development is very beneficial | 23 | 45% |
| 3 | Dismantling problems | 37 | 73% |
| | The problem of lack of compensation for demolition | 12 | 23% |
| 4 | Heritage House Status | 20 | 39% |
| | Status of Own Home | 19 | 37% |
| 5 | Status of Girik Land | 40 | 78% |
| | Land status unknown | 10 | 20% |
| 6 | worried about being displaced | 27 | 53% |
| | worried about not staying in the village | 19 | 37% |
| 7 | non-intrusive development | 19 | 37% |
| | disruptive development | 17 | 33% |
| 8 | impact (vibration, noise, dust) | 35 | 69% |

| | | |
|------------------------|----|-----|
| vibration impact alone | 13 | 25% |
|------------------------|----|-----|


Largest Survey Score 2




Graph image of the two largest scores

Equipment Condition

Damage to heavy equipment such as cranes and ships:



Equipment condition pictures



The image of the crane is not strong to suck

Equipment Inspection Pictures

The existence of damaged or old tools that are still in use greatly affects productivity, piling up spun piles, etc.

CONCLUSION

The project encounters several significant challenges that can impact its implementation and timely completion. The primary issue is the land status, which involves demolition, compensation, and environmental impacts like vibration and dust. Additionally, the absence of detailed Construction Safety Analysis (CSA) and Job Safety Analysis (JSA) work methods heightens the risk of work accidents, potentially causing material losses, casualties, and hindering project targets. The suboptimal condition of construction equipment, such as cranes and pontoons, further elevates the risk of accidents and delays. Social challenges, including community concerns related to evictions and environmental disturbances, add complexity to the project. Production efficiency also lags behind, with discrepancies between scheduled pile production capacity and actual field results, indicating obstacles to be addressed. The collective state of community relations, equipment, work methods, and CSA/K3 (Safety, Health, and Environment) standards interrelate, directly impacting project timelines. To enhance project success, several actions are recommended: developing more detailed work methods to mitigate work accidents and improve efficiency, performing regular maintenance on construction equipment to ensure optimal operation and minimize the risk of accidents and costly delays, and increasing community engagement to communicate project benefits and mitigation efforts. Furthermore, affected communities should receive prompt and fair compensation, with all land issues settled before the project begins to prevent future disruptions. The participation of all stakeholders, including community members, government agencies, security forces, and law enforcement, is essential for supporting the progress of this national strategic project. Additionally, fair compensation and, if necessary, alternative housing should be provided for those impacted by the project. Lastly, regular monitoring and

evaluation of project progress are necessary to ensure that production targets are met on schedule.

REFERENCE

- Ilovi dan tim (2023), Paparan Pre Construction Meeting (PCM) “PEMBANGUNAN PENGAMAN PANTAI DI PESISIR TELUK JAKARTA TAHAP 6 PAKET 4”.
- Arifin dan tim (2024), Laporan Progres Pembangunan Pengaman Pantai Dipesisir Teluk Jakarta tahap 6 paket 4, PT WIKA KSO HK.
- PMI Publisher (2017), A guide to the project management body of knowledge (PMBOK guide) / Project Management Institute.
- Nurhadi dan tim (2023), Laporan Pendahuluan Konsultan PT CEC KSO.
- Nurhadi dan tim (2023), Laporan Interim konsultan
- Riski dan tim (2024), Laporan Kerja Prektek Mahasiswa UI.
- Gunawan Lagowa (2012), Manajemen Proyek konstruksi, universitas trisakti.
- John ridley (2006), Ikhtisar Kesehatan Dan Keselamatan Kerja, Edisi 3 Erlangga.
- Manajemen Konstruksi, Mardiaman, cyntax computama, 2023.
- Suprpto (2024), Bahan kuliah K3, Bahan 1-10.
- Mardiaman (2023), Manajemen konstruksi, syntax computama.
- Mardiaman (2023), Metode Peralatan Konstruksi, syntax computama.